

15-119-10051-0000

Form CP-3
Rev. 6-4-68

KANSAS

JP
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
APR 25 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Cities Service Oil Co.

Complete Address Box 1098, Liberal, Kansas

Lease Name Novinger Well No. 508

Location SW NE Sec. 26 Twp. 33 Rge. 30 ~~(E)~~ (W)

County Meade Total Depth 5340'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated None

Plugging Contractor Toland & Johnston

Address Oklahoma City, Oklahoma License No. 539

Operation Completed: Hour 5:00PM Day 17 Month 4 Year 1972

The above well was plugged as follows:

13 3/8" to 663' circulated w/ cement. 8 5/8" to 2702' cemented.

5 1/2" to 5340' cemented. Top perforations 5308'

Spotted 20 sacks cement to 5100' Mud 5100' to 2000'

Spotted 45' sacks cement 2000' to 1900' Mud 1900' to 40'

Plug. Halls 7 10 sacks cement 40' to 0'. Company Pump

Pulled 3210' of 5 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

Signed: *Edgar A. Jones*
Well Plugging Supervisor

INVOICED

DATE 4-27-72

INV. NO. 5620-W