

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
APR 18 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Cities Service Oil Co.
Complete Address Box 1098, Liberal, Kansas
Lease Name Novinger Well No. 502
Location SW NW Sec. 26 Twp. 33 Rge. 30 (E) (W)
County Meade Total Depth 5904'
Abandoned Oil Well X Gas Well Input Well SWD Well D & A
Other well as hereafter indicated None
Plugging Contractor Toland & Johnston
Address Oklahoma City, Oklahoma License No. 539
Operation Completed: Hour 11:00AM Day 14 Month 4 Year 1972

The above well was plugged as follows:

13 3/8" to 2664' circulated w/ cement. 9 5/8" to 2688' cemented.
5 1/2" to 5370' cemented. Top perforations 5272'
Plug bottom w/ 20 sacks cement. Top of cement 5100'
Mud 5100' to 2000' Spotted 40 sacks cement 2000' to 1900'
Mud 1900' to 40' Plug, Hulls & 10 sacks cement 40' to 0'.
Pulled 3245' of 5 1/2" casing. Getco Pump Co.

I hereby certify that the above well was plugged as herein stated.

Signed: *Edward L. Eves*
Well Plugging Supervisor

INVOICED

DATE 4/18/72

INV. NO. 5580-W