

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
APR 25 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Cities Service Oil
Complete Address Box 1098, Liberal, Kansas
Lease Name Lanhofer Well No. 402
Location SE NE Sec. 27 Twp. 33 Rge. 30 (E) (W)
County Meade Total Depth 5322'
Abandoned Oil Well X Gas Well Input Well SWD Well D & A
Other well as hereafter indicated None
Plugging Contractor Toland & Johnston
Address Oklahoma City, Oklahoma License No. 539
Operation Completed: Hour 6:30PM Day 19 Month 4 Year 1972

The above well was plugged as follows:

13 3/8" to 627' circulated w/ cement. 8 5/8" to 2695' cemented.
5 1/2" to 5321' cemented. Top perforations 5277'
Plug bottom w/ 20 sacks cement Top of cement 5100'
Mud 5100' to 2000' Spotted 40 sacks cement 2000' to 1900'
Mud 1900' to 40' Plug, Halls & 10 sacks cement 40' to 0'
Pulled 2845' of 5 1/2" casing. Company pump

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 4-27-72
INV. NO. 5619-24