

KANSAS

KS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
MAY 2 - 1972
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Cities Service Oil Co.

Complete Address Box 1098, Liberal, Kansas

Lease Name Vail Well No. 702

Location NE ~~NE~~ NW Sec. 35 Twp. 33 Rge. 30 (E) (W)

County Meade Total Depth 5373'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated None

Plugging Contractor Toland & Hohnston

Address Oklahoma City, Oklahoma License No. 539

Operation Completed: Hour 5:00pm Day 25 Month 5 Year 1972

The above well was plugged as follows:

- 13 3/8" to 632' circulated w/ cement. 8 5/8" to 2724' cemented.
- 5 1/2" to 5371' cemented. Top perforations 5304'
- Plug bottom w/ 20 sacks cement. Top pf cement 5100'
- Mud 5100' to 2000' Spot 40 sacks cement 2000' to 1900'.
- Mud 1900' to 40' Plug, HULLS& 10 sacks cement 40' to 0'.
- Company Pump Pulled 3019' of 5 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

Signed: *Edgar J. Eves*
Well Plugging Supervisor

INVOICED

DATE 5-3-72

INV. NO. 56610-11