

15-129-20036-00-00

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
APR 9 1969
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Anadarko Production Company

Complete Address: Box 351, Liberal, Kansas

Lease Name Hayward "B" Well No. 1

Location C SE NW Sec. 5 Twp. 33 Rge. 39 (E) (W)

County Morton Total Depth 6514'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: None

Plugging Contractor: Lohmann-Johnson Drilling Co.

Address: 1737 Wichita Plaza, Wichita, Kansas License No.

Operation Completed: Hour 5:00 PM Day 6 Month 4 Year 1969

The Above well was plugged as follows:

8 5/8" to 1673' circulated w/ cement. Mud 6514' to 1700'

Spotted 40 sacks cement 1700' to 1600' Mud 1600' to 900'

Spotted 35 sacks cement 900' to 800' Mud 800' to 45'

Plug, Hulls & 15 sacks cement 45' to 0'. Dowell Pump Truck.

I hereby certify that the above well was plugged as herein stated.

Signed: Edgar J. Ford
Well Plugging Supervisor

INVOICED

DATE 4/9/69
INV. NO. 9572-W