

15-189-00488-00-00

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JAN 27 1969
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Ashland Oil & Refining Company

Complete Address: Box 127, Satanta, Kansas 67870

Lease Name J.A. Christopher Well No. 1

Location C NW Sec. 14 Twp. 33 Rge. 39 (E) (W)

County Stevens Total Depth 2652'

Abandoned Oil Well Gas Well X Input Well SWD Well D & A X

Other well as hereafter indicated: None

Plugging Contractor: Sargents Casing Pulling Co.

Address: Box 506, Liberal, Kansas License No. 511

Operation Completed: Hour 11:00A Day 24 Month 1 Year 1969

The Above well was plugged as follows:

13 3/8" to 505' circulated w/ cement. 7" to 2440' cemented.

5 1/2" liner 2390' to 2652' Plug bottom w/ 25 sacks cement

Top of cement 2340' Mud 2340' to 525'

Spotted 55 sacks cement 525' to 400' Mud 400' to 30'

Plug, Halls & 15 sacks cement 30' to 0'. Company Pump

Pulled 1207' of 7" casing.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 1/27/69

INV. NO. 9242-W