

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-129- 20,554-00-00

200 Colorado Derby Building  
Wichita, KS 67202

Operator's Full Name Anadarko Oil Co

Complete Address Box 351 Liberal Kansas (Div) 67901

Lease Name Schmidt Well No. B1

Location 1250' ESL-1250' FWL Sec. 5 Twp. 33 Rge. 39 (East)(West)

County Morton Total Depth 6147'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated This well was completed but not produced

Plugging Contractor Sargants Casing Pulling Service

Address 620 S Lincoln Box 506 Liberal Kansas 67901 License No. 511

Operation Completed: Hour: 11:30 AM Day: 3 Month: March Year: 1982

Plugging Operations attended by Agent?: All  Part  None

The above well was plugged as follows:

*There is 6142' of 4 1/2" production pipe cemented & plugged back to 5930'. These operations are from 5875' to 5880'. 1st plug cemented off bottom with 20 sby of cement. 2nd plug at 1650' with 50 sby of cement. 3rd plug at 620' with 25 sby of cement. 4th plug 40' to 0' on solid bridge with 10 sby of cement. The cement was pumped down through production pipe as they came out of the hole with it. The plugging was accomplished by Sargants Casing pulling service. They recovered 3627' of 4 1/2" production pipe.*

Amount of Surface Casing: 1654' of 8 1/8" cement circulated

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Paul Luthie  
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

RECEIVED  
STATE CORPORATION COMMISSION  
3-9-82  
MAR - 9 1982  
CONSERVATION DIVISION  
Wichita Kansas

INVOICED

DATE 3-10-82

INV. NO. 9600-W

Signed: Paul Luthie  
Conservation Division Agent