

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-035-01772-00-01  
Spot: SESENE Sec/Twnshp/Rge: 17-35S-7E  
2724 feet from S Section Line, 126 feet from E Section Line  
Lease Name: DOROTHY (OWWO) Well #: 3  
County: COWLEY Total Vertical Depth: 2671 feet

Operator License No.: 4555  
Op Name: ROADRUNNER ENERGY, INC.  
Address: 6906 E 108TH ST  
TULSA, OK 74133

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2671		150 SX
SURF	8.625	100		75 SX

Well Type: SWD UIC Docket No: D22003.0 Date/Time to Plug: 01/15/2015 12:00 PM  
Plug Co. License No.: 31539 Plug Co. Name: SAMS WELL SERVICE, INC.  
Proposal Rcvd. from: JAMES GAFFNEY Company: ROADRUNNER ENERGY Phone: (918) 527-9247

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 01/15/2015 12:00 PM KCC Agent: JONATHAN HILL

Actual Plugging Report:

1) CIBP SET BY ELITE WIRELINE AT 1300'. 2) RAN GR/CBL LOG TO VERIFY 5.5" PRODUCTION CASING WAS CEMENTED FROM 400' TO SURFACE. 3) BAILED 2 SXS CEMENT ON TOP OF CIBP. 4) RAN TUBING IN HOLE TO 350'/PUMPED APPROX 120 SXS OF 60/40 POZ CEMENT WITH 4% CACL AND CIRCUALTED TO SURFACE. 5) PULLED TUBING OUT OF HOLE AND TOPPED OFF BACK TO SURFACE WITH APPROX. 30 SXS (150 TOTAL).

Perfs:

Top	Bot	Thru	Comments
2515	2525		CSG
1465	2475		CSG
1358	1384		CSG
1320	1334		CSG
0	0		CSG

Remarks: CEMENTING COMPLETED BY CONSOLIDATED OIL WELL SERVICES, BARTLESVILLE, OK, TICKET #: 673

Plugged through: TBG

CKM 2/4/15

District: 02

Signed Jonathan Hill  
CC: UIC ✓ (TECHNICIAN)

Received  
KANSAS CORPORATION COMMISSION

Form CP-2/3

JAN 29 2015

CONSERVATION DIVISION  
WICHITA, KS

JK