

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-035-23798-00-00  
Spot: SWSWSW Sec/Twnshp/Rge: 16-35S-7E  
558 feet from S Section Line, 5011 feet from E Section Line  
Lease Name: DOROTHY Well #: 12  
County: COWLEY Total Vertical Depth: 2990 feet

Operator License No.: 4555  
Op Name: ROADRUNNER ENERGY, INC.  
Address: 6906 E 108TH ST  
TULSA, OK 74133

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1949		
CIBP		2265		
PROD	5.5	2986		225 SX
SURF	8.625	297		185 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/01/2014 8:00 AM  
Plug Co. License No.: 31539 Plug Co. Name: SAMS WELL SERVICE, INC.  
Proposal Rcvd. from: JAMES GAFFNEY Company: ROADRUNNER ENERGY Phone: (918) 527-9247

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 01/15/2015 12:00 PM KCC Agent: JONATHAN HILL

Actual Plugging Report:

1) CIBP SET AT 1949'. 2) CASING PERFORATED AT APPROX 350'. 3) BAILED 2 SKS CEMENT ON TOP OF CIBP. 4) RAN TUBING IN TO 353' AND PUMPED 200 SXS 60/40 POZ WITH 4% CACL. CEMENT CIRCUALTED UP 5.5" CASING TO SURFACE - CASING SHUT IN - CEMENT THEN CIRCUALTED UP BACKSIDE OF 5.5" TO SURFACE. 5) PULLED TUBING OUT OF HOLE AND TOPPED OFF BACK TO SURFACE WITH APPROX 15 SXS (215 TOTAL).

Perfs:

Top	Bot	Thru	Comments
2232	2248	CSG	
2038	2048	CSG	

Remarks: CEMENTING COMPLETED BY CONSOLIDATED OIL WELL SERVICES, BARTLESVILLE, OK TICKET #674.

Plugged through: TBG

*CKM 2/4/15*

District: 02

Signed Jonathan Hill

(TECHNICIAN)

Received  
KANSAS CORPORATION COMMISSION

JAN 29 2015

CONSERVATION DIVISION  
WICHITA, KS