

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-23514-00-00
Spot: N2 Sec/Twnshp/Rge: 30-26S-8E
1650 feet from S Section Line, 5610 feet from E Section Line
Lease Name: DRUMM INSTITUTE Well #: 3
County: BUTLER Total Vertical Depth: 2869 feet

Operator License No.: 34569
Op Name: SONOMA RESOURCES LLC
Address: PO BOX 384
EL DORADO, KS 67042

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2869		225 SX
SURF	8.625	253		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/14/2015 12:00 PM
Plug Co. License No.: 34928 Plug Co. Name: IRON HORSE WELL SERVICE LLC
Proposal Rcvd. from: DAN FLOWERS, SONOMA Company: IRON HORSE WELL SERVICE LLC Phone: (316) 208-7590

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JONATHAN HILL WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/14/2015 12:00 PM KCC Agent: JONATHAN HILL

Actual Plugging Report:

1) CIBP SET AT 2662' AND CAPPED W/ 2 SXS CEMENT. 2) CASING PERFORATED AT APPROX. 303' BY CORNISH WIRELINE, CHANUTE, KS. 3) PUMPED 93 SXS OF 60/40 POZ CEMENT WITH 2% CACL AND 0.5 LB/SK OF POLY FLAKE AND CIRCUALTED TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
2721	2731	CSG	
2712	2718	CSG	

Remarks: CEMENTING COMPLETED BY CONSOLIDATED OIL WELL SERVICES. TICKET #48554. PLUGGED DUE TO COMPLIANCE K.A.R. 82-3-111.

Plugged through: CSG

CXM 2/4/15

District: 02

Signed Jonathan Hill

(TECHNICIAN)
KANSAS CORPORATION COMMISSION

JAN 29 2015

Form CP-2/3

CONSERVATION DIVISION
WICHITA, KS

JH