

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-035-19388-00-01
Spot: NESENE Sec/Twnshp/Rge: 10-32S-7E
3614 feet from S Section Line, 351 feet from E Section Line
Lease Name: BEAMER Well #: 2
County: COWLEY Total Vertical Depth: 2175 feet

Operator License No.: 6101
Op Name: TEICHGRAEBER OIL, INC.
Address: 700 N MAIN ST
EUREKA, KS 67045

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2175		CEMENTED 300' TO SURFACE
SURF	8.625	60		0 SX

Well Type: EOR UIC Docket No: E06951.4 Date/Time to Plug: 01/12/2015 12:00 PM
Plug Co. License No.: 9386 Plug Co. Name: GUS JONES CABLE TOOL SERVICE, LLC
Proposal Rcvd. from: RICK STOUT Company: TEICHGRAEBER OIL Phone: (620) 583-7500

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK Witness Type: PARTIAL
Date/Time Plugging Completed: 01/12/2015 12:00 PM KCC Agent: JONATHAN HILL

Actual Plugging Report:

1) CIBP SET AT 1879' (JUNK IN HOLE AT 1908') AND CAPPED WITH 10 SXS OF 60/40 POZ W/ 4% CACL CEMENT PUMPED THROUGH TUBING. 2) TUBING RAN UP TO 350', THEN PUMPED APPROX. 50 SXS CEMENT AND CIRCULATED TO SURFACE. 3) CEMENT FELL APPROX. 80' FROM SURFACE (DETERMINED BY WIRELINE). 4) TOPPED OFF TO SURFACE W/ APPROX. 10 SXS CEMENT ON 1/12/2015.

Perfs:

Top	Bot	Thru	Comments
2147	2153	CSG	

Remarks: CEMENTING COMPLETED BY ELITE SERVICES, TICKET #2054.

Plugged through: TBG

CFM 2/4/15

District: 02

Signed Jonathan Hill
(TECHNICIAN)

cc: uic ✓

Received
KANSAS CORPORATION COMMISSION

Form CP-2/3

JAN 29 2015

CONSERVATION DIVISION
WICHITA, KS

JK