

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-007-23101-00-00
Spot: SWNESE Sec/Twnshp/Rge: 22-31S-13W
1663 feet from S Section Line, 965 feet from E Section Line
Lease Name: PACKARD Well #: 2-22
County: BARBER Total Vertical Depth: 4330 feet

Operator License No.: 34886
Op Name: TOTO ENERGY, LLC
Address: 25815 OAK RIDGE DR
SPRING, TX 77380

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3560		WITH 2 SX CMT
CIBP	4.5	3655		
CIBP	4.5	4195		
PROD	4.5	4330	1500	WITH 185 SX CMT
SURF	8.625	221		WITH 200 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 01/12/2015 2:00 PM
Plug Co. License No.: 34879 Plug Co. Name: CANAAN WELL SERVICE INC.
Proposal Rcvd. from: AARON FROMAN Company: CANAAN WELL SERVICE INC. Phone: (620) 440-0170

Proposed Plugging Method: SET CIBP @ 3550' & 2 SX CMT. PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. PLUG AT 270' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: ROBERT DICKERSON WitnessType: PARTIAL
Date/Time Plugging Completed: 01/12/2015 5:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 3560' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. 1ST PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 275' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4229	4236		
4195			
3670	3671		
3655			
3597	3622		

RECEIVED
KANSAS CORPORATION COMMISSION

FEB 02 2015

CONSERVATION DIVISION
WICHITA, KS

Remarks: **COMPLIANCE ISSUE: DENIED TA NEED FL** USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: CSG

District: 01

RECEIVED
JAN 21 2015
KCC DODGE CITY

Signed _____

(TECHNICIAN)

CKM 2/4/15