

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-40462-00-00
Spot: SE Sec/Twnshp/Rge: 17-28S-4E
2145 feet from S Section Line, 1815 feet from E Section Line
Lease Name: KIRKPATRICK Well #: 1X
County: BUTLER Total Vertical Depth: 2293 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2293		
PROD	5.5	0		0 SX
PROD	5.5	2400		
SURF	8.625	0		0 SX
SURF	8.625	200		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/27/2015 9:30 AM
Plug Co. License No.: 32991 Plug Co. Name: SIMMONS WELL SERVICE, INC.
Proposal Rcvd. from: CASEY COATS Company: VESS OIL CORPORATION Phone: (316) 655-1997

Proposed
Plugging
Method:

AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/27/2015 12:00 PM KCC Agent: JONATHAN HILL

Actual Plugging Report:

1) RAN IN HOLE WITH TUBING TO 1930' (ESTIMATED KC PERFS) AND PUMP 35 SXS OF 60/40 4% CEMENT WITH 1% CACL, PULLED TUBING UP TO APPROX. 1000' AND LET CEMENT SET UP FOR APPROX. 1.5 HOURS. TAGGED CEMENT WITH WIRELINE AT 1540'. 2) PUMPED 35 SXS OF CEMENT AT 1000', PULL TUBING OUT OF HOLE, AND LET SET UP FOR APPROX. 1.5 HOURS. TAGGED TOP AT 664' WITH WIRELINE. 3) PRESSURED UP AND HELD 300 PSI. RAN IN HOLE WITH WIRELINE AND PERFORATED AT 275'. PUMPED 90 SXS CEMENT AND CIRCULATED TO SURFACE AND SHUT IN CASING.

Perfs:

Top	Bot	Thru	Comments
1940	1950		

RECEIVED
KANSAS CORPORATION COMMISSION
FEB 02 2015
CONSERVATION DIVISION
WICHITA, KS

Remarks: CEMENTING COMPLETED BY CONSOLIDATED WELL SERVICES, EL DORADO, KS. TICKET #48326.
HISTORY ON WELL NOT KNOWN.

Plugged through: TBG

CKM 2/4/15

District: 02

Signed

Jonathan Hill

(TECHNICIAN)