

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-007-00494-00-01
Spot: SESESE Sec/Twnshp/Rge: 4-30S-11W
330 feet from S Section Line, 330 feet from E Section Line
Lease Name: COSS UNIT Well #: 1
County: BARBER Total Vertical Depth: 4880 feet

Operator License No.: 33168
Op Name: WOOLSEY OPERATING COMPANY, LL
Address: 125 N MARKET STE 1000
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2796		
PROD	4.5	4880	1980	WITH 175 SX CMT
SURF	8.625	394		WITH 300 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 01/06/2015 11:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: PUMP DOWN 4 1/2" CASING WITH 200# HULLS & 25 SX CMT TO 2630'. PLUG AT 670' WITH 10 SX GEL & 50 SX CMT. PLUG AT 425' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: ROBERT DICKERSON WitnessType: NONE
Date/Time Plugging Completed: 01/06/2015 5:30 PM KCC Agent: ROBERT DICKERSON

Actual Plugging Report:

PUMP DOWN 4 1/2" CASING WITH 200# HULLS & 25 SX CMT TO 2630'. PRESSURED TO 700 PSI. 1ST PLUG AT 670' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 425' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 30 SX CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
2724	2734		

RECEIVED
KANSAS CORPORATION COMMISSION
FEB 02 2015
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

CCM 2/14/15

District: 01

Signed Robert Dickerson
(TECHNICIAN)

RECEIVED
JAN 23 2015
KCC DODGE CITY

[Signature]