

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-007-20742-00-02
Spot: SEWNNE Sec/Twnshp/Rge: 7-30S-11W
4244 feet from S Section Line, 1661 feet from E Section Line
Lease Name: FRANKLIN HOUSE SWD Well #: 1
County: BARBER Total Vertical Depth: 2835 feet

Operator License No.: 33168
Op Name: WOOLSEY OPERATING COMPANY, LL
Address: 125 N MARKET STE 1000
WICHITA, KS 67202

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|-----------------|
| PROD | 4.5 | 2835 | 2000 | WITH 150 SX CMT |
| SURF | 8.625 | 256 | | WITH 200 SX CMT |

Well Type: SWD UIC Docket No: D28048.0 Date/Time to Plug: 12/23/2014 10:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DAVID BRADY Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: NONE
Date/Time Plugging Completed: 12/23/2014 12:30 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PUMP 200# HULLS & 25 SX CMT. DISPLACE WITH WATER TO 2600'. SHUT IN AT 500 PSI. 1ST PLUG AT 780' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 300' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT. TOPPED OFF WITH 20 SX CMT.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 2758 | 2799 | | |

RECEIVED
KANSAS CORPORATION COMMISSION
FEB 02 2015
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

ccm dallas

District: 01

Signed *Stephen J Pfeifer*
cc:uic (TECHNICIAN)

RECEIVED
JAN 26 2015 *NP*
KCC DODGE CITY