

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-007-21211-00-00
Spot: NWSW Sec/Twnshp/Rge: 33-34S-13W
1980 feet from S Section Line, 480 feet from W Section Line
Lease Name: ALLEN Well #: 1
County: BARBER Total Vertical Depth: 4972 feet

Operator License No.: 33168
Op Name: WOOLSEY OPERATING COMPANY, LL
Address: 125 N MARKET STE 1000
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4870	2025	WITH 400 SX CMT
SURF	8.625	372		WITH 350 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 01/16/2015 4:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DAVID BRADY Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: PUMP 25 SX CMT & 200# HULLS. PLUG AT 700' WITH 10 SX GEL & 50 SX CMT. PLUG AT 400' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: NONE
Date/Time Plugging Completed: 01/16/2015 5:30 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:
PUMP DOWN 4 1/2" CASING 200# HULLS & 25 SX CMT. DISPLACED WITH 71 BBLS WATER. SHUT IN AT 250#. 1ST PLUG AT 700' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 400' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4944	4954		
4910	4920		
4894	4906		

RECEIVED
KANSAS CORPORATION COMMISSION
FEB 02 2015
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.
Plugged through: CSG

District: 01

Signed Kenny M Sullivan (TECHNICIAN) 2/04/15

RECEIVED
JAN 24 2015
KCC DODGE CITY

Form CP-2/3