

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-007-20394-00-00
Spot: SW Sec/Twnshp/Rge: 3-30S-11W
1360 feet from S Section Line, 1315 feet from W Section Line
Lease Name: ROLF A. LOREN Well #: 1
County: BARBER Total Vertical Depth: 2966 feet

Operator License No.: 33168
Op Name: WOOLSEY OPERATING COMPANY, LL
Address: 125 N MARKET STE 1000
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2964	2006	WITH 100 SX CMT
SURF	8.625	244		WITH 200 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 01/02/2015 10:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SET CIBP @ 2660' & 2 SX CMT. PLUG AT 660' WITH 10 SX GEL & 50 SX CMT. PLUG AT 280' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/02/2015 2:30 PM KCC Agent: ROBERT DICKERSON

Actual Plugging Report:
PUMP DOWN 4 1/2" CASING WITH 200# HULLS & 25 SX CMT. SHUT IN WITH 800 PSI. TAGGED TOC @ 2470'. 1ST PLUG AT 674' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 278' WITH 50 SX CMT. 3RD PLUG AT 33' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2713	2731		

RECEIVED
KANSAS CORPORATION COMMISSION
FEB 02 2015
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.
Plugged through: CSG

2/4/15 CRM

District: 01

Signed Robert Dickerson
(TECHNICIAN)

RECEIVED
JAN 23 2015
KCC DODGE CITY

Form CP-2/3