

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-007-20612-00-00
Spot: SENWSE Sec/Twnshp/Rge: 6-30S-11W
1634 feet from S Section Line, 1658 feet from E Section Line
Lease Name: ROLF AMY A Well #: 1
County: BARBER Total Vertical Depth: 3002 feet

Operator License No.: 33168
Op Name: WOOLSEY OPERATING COMPANY, LL
Address: 125 N MARKET STE 1000
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2975	2000	WITH 150 SX CMT
SURF	8.625	284		WITH 225 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 01/13/2015 9:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: ROBERT MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: PUMP 25 SX CMT & 200# HULLS ON BOTTOM. PLUG AT 660' WITH 10 SX GEL & 50 SX CMT. PLUG AT 330' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/13/2015 10:45 AM KCC Agent: ROBERT DICKERSON

Actual Plugging Report:

PUMP 25 SX CMT & 200# HULLS AT 2700'. SHUT IN WITH 500 PSI. TAGGED TOC @ 2630'. 1ST PLUG AT 680' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 320' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2751	2776		

RECEIVED
KANSAS CORPORATION COMMISSION
FEB 02 2015
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

District: 01

Signed

Robert Dickerson

(TECHNICIAN)

RECEIVED
JAN 21 2015
KCC DODGE CITY

Form CP-2/3