

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-007-22679-00-00
Spot: NESWNW Sec/Twnshp/Rge: 29-32S-12W
1628 feet from N Section Line, 915 feet from W Section Line
Lease Name: WARWICK Well #: 5
County: BARBER Total Vertical Depth: 5059 feet

Operator License No.: 33168
Op Name: WOOLSEY OPERATING COMPANY, LL
Address: 125 N MARKET STE 1000
WICHITA, KS 67202

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|-----------------|
| PROD | 4.5 | 5054 | 3125 | WITH 150 SX CMT |
| SURF | 8.625 | 250 | | WITH 175 SX CMT |

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 01/15/2015 3:30 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: PUMP 25 SX CMT & 200# HULLS. PLUG AT 660' WITH 10 SX GEL & 50 SX CMT. PLUG AT 280' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: PARTIAL
Date/Time Plugging Completed: 01/15/2015 5:30 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PUMPED DOWN 4 1/2" CASING WITH 200# HULLS & 25 SX CMT. TOC @ 4415'. 1ST PLUG AT 630' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 294' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT. TOPPED OFF WITH 5 SX CMT.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 4514 | 4568 | | |

RECEIVED
KANSAS CORPORATION COMMISSION
FEB 02 2015
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

2/4/15 CKM

District: 01

Signed Stephen J Pfeifer
(TECHNICIAN)

RECEIVED
JAN 24 2015
KCC DODGE CITY

54