

1080298

TO: STATE CORPORATION COMMISSION

API NUMBER 15-093-00626 0000
C SE SEC. 31, T 22 S, R 37 W

CONSERVATION DIVISION - PLUGGING SECTION 1320 FEET FROM SOUTH SECTION LINE
WICHITA STATE OFFICE BLDG., 130 S. MARKET 1320 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME MODIE WELL # 22
TECHNICIAN'S PLUGGING REPORT 3/28 COUNTY KEARNY 85.51
OPERATOR LICENSE # 5249 WELL TOTAL DEPTH 2631 FEET

OPERATOR: OSBORN HEIRS COMPANY PRODUCTION CSG: SIZE 5 1/2" @ 2564' WITH 100 SX
NAME AND PO BOX 39 SURFACE CASING: SIZE 8 5/8" @ 305' WITH 150 SX
ADDRESS KENDALL, KS 67857

RECEIVED
STATE CORPORATION COMMISSION
04-12-00 Rev
APR 12 2000
SWD WELL D/A

ABANDONED OIL WELL GAS WELL INPUT WELL OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR HALLIBURTON ENERGY SERVICE Wichita LICENSE NUMBER NA
ADDRESS LIBERAL, KS 67901

COMPANY TO PLUG AT: HOUR: 8:00 AM DAY: 28 MONTH: 03 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM _____
(COMPANY NAME) HALLIBURTON ENERGY SERVICE (PHONE) 316-624-3879

WERE: 4 1/2 SLOTTED LINER IN OPEN HOLE FROM 2564-2631

SET CIBP AT 2500' WITH 2 SX CEMENT ON TOP. PRESSURE TESTED CASING TO 500# PERFORATED @
1046' TO 1047' 4 HOLES, RAN INJECTION RATE 2 BPM @ 400#. STARTED CEMENT DOWN 5 1/2 HALLIBURTON
PUMPED 195 SX CEMENT. MAXIMUM PSI 500#. SHUT IN WITH 100#. PUMPED DOWN 8 5/8 X 5 1/2 ANNULUS
250 SX CEMENT. MAXIMUM PSI 800#. SHUT IN @ 100#.

PLUGGING PROPOSAL RECEIVED BY KEVIN STRUBE

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE

OPERATIONS COMPLETED: HOUR: 2:00 PM DAY: 28 MONTH: 03 YEAR: 2000

ACTUAL PLUGGING REPORT _____

SET CIBP AT 2500' WITH 2 SX CEMENT ON TOP. PRESSURE TESTED CASING TO 500# PERFORATED AT
1046' TO 1047' 4 HOLES, RAN INJECTION RATE 2 BPM @ 400#. STARTED CEMENT DOWN 5 1/2 BY
HALLIBURTON PUMPED 195 SX CEMENT. MAXIMUM PSI 500#. SHUT IN @ 100#. PUMPED DOWN 8 5/8 X 5 1/2
ANNULUS 250 SX CEMENT. MAXIMUM PSI 800#. SHUT IN @ 100#.

REMARKS: USED 60/40 POZMIX 6% GEL BY HALLIBURTON. NO CASING RECOVERED.
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING. INVOICED
DATE 4/14/00 SIGNED Kevin D Strube (TECHNICIAN) FORM CP-2/3

WELL NO. 061550