

3-21

215

To: 1 040253
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION W/2 W/2 SW, SEC. 5, T 27 S, R 15 W/EX
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-151-20,995-00-00
1320 feet from S section line

TECHNICIAN'S PLUGGING REPORT

4950 feet from E section line

Operator License # 5364

Lease Name Mollie Well # 1

Operator: Beren Corporation

County Pratt 148.53

Name & Address Box 723

Well Total Depth 4570 feet

Hays, KS 67601

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 446

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105

Address P.O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 9:30 a.m. Day: 21 Month: 3 Year: 19 89

Plugging proposal received from Elmo Morgenstern

(company name) Clarke Corporation (phone) 316-886-5665

were: 4 1/2" at 4569' PBD 4540' Perfs at 4447-4452'

1st plug sand back to 4400' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 130 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

MAR 28 1989
03-28-89

Plugging Proposal Received by James R. Kapp (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Hour: 10:15 a.m. Day: 21 Month: 3 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded back to 4400' and dumped 4 sx cement on top of sand bridge with bailer,

2nd plug pumped down 8 5/8" surface pipe with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 130 sx cement.

Maximum pressure 600 psi and shut in 300 psi.

Remarks: Used 60/40 Pozmix 2% gel 2% cc by B.J. Titan. Recovered 2700' of 4 1/2" casing. (If additional description is necessary, use BACK of this form.)

INVOLVED

(If applicable) observe this plugging.

Signed Stephen J. Pfeifer (TECHNICIAN)

DATE 3-30-89

INV. NO. 24290