

1 060578

R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 151-21,195-00-00

SW SW NW , SEC. 5 , T 27 S, R 15 W/X

2970 feet from S section line

4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Lease Name Smith 'pp' Well # 1

Operator: TXO Production Corp.

County Pratt 149.50

Name & Address 200 West Douglas, Suite 300

Well Total Depth 4600 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 411

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Clarke Corporation License Number 5105

Address Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 1:00 pm Day: 29 Month: May Year: 19 85

Plugging proposal received from Elmo Morgenstern

(company name) Clarke (phone) 316-886-5665

were: 4 1/2" at 4599' PBSD 4160' Perfs at 4126-32 & 4164-68'

1st plug sand back to 4075' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 150 sx cement.

Plugging Proposal Received by Paul A. Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All x Part None

Operations Completed: Hour: 2:30 pm Day: 29 Month: May Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 4075' and dumped 4 sx cement on top of

sand through bailer, 2nd plug squeezed well with 3 sx hulls, 15 sx gel, 50 sx cement, 10

sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 150 sx cement.

STATE CORPORATION COMMISSION
05-31-85
MAY 31 1985

Maximum pressure 400 psi and shut in 250 psi.

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Recovered 2400' 4 1/2" casing. Used 60/40 Pozmix 2% gel 3% cc by BI-Titan (If additional description is necessary, use BACK of this form.)

INVOICED

(old / xxxxxx) observe this plugging.

DATE 6-6-85

Signed Paula A. Luthi (TECHNICIAN)

INV. NO. 8355

5-29