

1 080506

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 151-21,247 - 00-00
SW NW NW, SEC. 5, T27 S, R 15 (W/E)

4290 feet from S section line
4930 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Lease Name Smith "PP" Well # 2

Operator: TXO Production Corp.

County Pratt 149.63

Name & Address 155 N. Market, Suite 1000
Wichita, KS 67202

Well Total Depth 4604 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 403

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor TXO Production Corp. License Number 5171

Address 155 N. Market, Suite 1000, Wichita, KS 67202

Company to plug at: Hour: 10:00 am Day: 25 Month: March Year: 19 86

Plugging proposal received from Rex Cravens

(company name) TXO (phone) 316-269-7600

were: 4 1/2" at 4603' Perfs at 4514-22'; 4526-30'

1st plug down 4 1/2" with 1 sack hulls and 20 sx cement, 22 sx gel and 70 sx cement

2nd plug pump 125 sx cement down annulus

Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:00 am Day: 25 Month: March Year: 19 86

ACTUAL PLUGGING REPORT 1st plug pumped 1 sack hulls, 20 sx cement, 10 sx gel, 43 bbls slurry

9# mud, and 70 sx cement Maximum pressure 350 psi and shut in 100 psi

2nd plug pumped 125 sx cement down backside maximum pressure 350 psi and shut in 75 psi

REV
STATE OF KANSAS
04-07-86
APR - 7 1986

Remarks: No recovery. Used 60/40 Pozmix 6% gel by BJ-Titan.
(If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION
Wichita, Kansas

INVOICED observe this plugging.

DATE APR 7 1986

Signed J. H. [Signature] (TECHNICIAN)

INV. NO. 13322

3-23 MAY 13 1986