

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-151-21,234-0000  
SUNE4, Sec. 3, T 27 S, R 15 W1X  
1980 feet from N1X section line

TECHNICIAN'S PLUGGING REPORT

1980 feet from X/E section line

Operator License # 5087

Lease Name STOTTS Well # 1-3

Operator: Texas Energies, Inc.  
Name & Address P.O. Box 947  
Pratt, KS 67124

County Pratt

Well Total Depth 1010 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 7/8 feet 330

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Wheatstate Drilling License Number 5149

Address P.O. Box 329, Pratt, KS 67124

Company to plug at: Hour: 10:00 AM Day: 6 Month: Jan Year: 19 83

VERBAL PLUGGING ORDERS GIVEN TO TED MOFF

(company name) Wheatstate (phone) 672-7574(516)

were on 1-2-83 circ. lost @ 1002', 75 o/cmt set @ 673'.  
Lost circ @ 525-907', plug drilled out & lost circ @  
at 890'. On 1-3-83 set 75 o/cmt at 673' but hole  
would not load. Another 50 o/cmt set @ 525' and  
plug held. Drilled plug out and lost circ @  
900'.

Signed \_\_\_\_\_  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 12:45 pm Day: 6 Month: Jan Year: 19 83

ACTUAL PLUGGING REPORT

on 1-4-83, set 100 o/cmt at  
673', drilled out plug and lost circ @ 907'.  
150 o/cmt set @ 820'. Wirelined top @ 350'.  
Issued orders to set 85 o/c 50/50 Bynip, 40 gal-32cc  
from 350'-0' and well plugged as ordered. Cementing  
by Halliburton. 10 o/cmt circ. in the mouse hole  
and rat hole.

Remarks: Wheatstate did not notify or receive orders  
from KCC for any plugs set in lost circ zone

I hereby certify that the above plugging instructions were given as herein stated

and that I ~~did~~ / did not RECEIVED this plugging.

STATE CORPORATION COMMISSION

JAN 14 1983

CONSERVATION DIVISION  
Wichita, Kansas

Signed R. Brantner  
(TECHNICIAN)

FORM CP-2/3  
Rev. 9-82

INVOICED  
DATE 3-2-83  
CASH NO. 2460-W