

1 050634

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 151-21,339-00-00

C NW NE , SEC. 3 , T 27 S, R 15 (W/E)
4620 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5151

Lease Name Seyfert Well # 2-3

Operator: Gear Petroleum Co., Inc.
Name & Address 300 Sutton Place
Wichita, KS 67202

County Pratt 147.45
Well Total Depth 4537 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 343

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050
Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 9:00 am Day: 3 Month: October Year: 19 85

Plugging proposal received from Roger Losket
(company name) Kelso (phone) 316-938-2457

were: 4 1/2" at 4137' PBD 4137' Perfs at 3926-30'

1st plug pump 1 sack hulls and 30 sx cement to bottom

2nd plug squeeze well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,
release 8 5/8" rubber plug and pump 125 sx cement.

660 FAL
1060 FEL

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:21 am Day: 3 Month: October Year: 19 85

ACTUAL PLUGGING REPORT 1st plug pumped 30 sx cement at 3810', 2nd plug squeezed well
with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber
plug and pumped 125 sx cement.

Maximum pressure 300 psi and shut in 100 psi

Remarks: Recovered 2200' 4 1/2" casing. Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED RECEIVED
STATE CORPORATION COMMISSION

DATE 10-15-85
INV. NO. 10569

OCT 10 1985
10-10-85
CONSERVATION DIVISION

Signed Richard W. Lacey (TECHNICIAN)