

1040245 3-15 93 R

To: STATE CORPORATION COMMISSION CONSERVATION DIVISION - PLUGGING SECTION App. SW NW NE SEC. 35, T 27 S, R 14 W/E 200 COLORADO DERBY BUILDING WICHITA, KANSAS. 67202

API NUMBER 15- 151-21,763-00-00 4130 feet from S section line 2474 feet from E section line

TECHNICIAN'S PLUGGING REPORT Operator License 5893 Lease Name Krueger Well 4

Operator: Pratt Well Service, Inc. Name & Address P.O. Box 847 Pratt, KS 67124

RECEIVED STATE CORPORATION COMMISSION MAR 21 1989 03-21-89 CONSERVATION DIVISION Wichita, Kansas

County Pratt Well Total Depth 4701 feet

Conductor Pipe: Size feet face Casing: Size 10 3/4 feet 331

Abandoned Oil Well X Gas Well Input Well SWD Well D&A Other well as hereinafter indicated

Plugging Contractor Pratt Well Service, Inc. License Number 5893 Address P.O. Box 847, Pratt, KS 67124

Company to plug at: Hour: 10:15 a.m. Day: 15 Month: 3 Year: 19 89

Plugging proposal received from Bruce Wagner (company name) Pratt Well Service, Inc. (phone) 316-672-2531

were: 7" at 4630' Open hole from 4630-4701' and Perfs at 4421-27, 4378-86', Model D Packer 1st plug sand back to 4280' and dump 7 sx cement on top of sand through bailer, at 4590' 2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 10 3/4" wiper plug and pumped 125 sx cement.

Plugging Proposal Received by Dan Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 10:45 a.m. Day: 15 Month: 3 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded back to 4280' and dumped 7 sx cement on top of sand through bailer,

2nd plug pumped down 10 3/4" surface pipe with 400 lbs. hulls, 12 sx gel, 60 sx cement, 12 sx gel, 100 lbs. hulls and 140 sx cement.

Maximum pressure 300 psi and shut in 50 psi.

Had been a dual completion at one time.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 2013' of 7" casing. (If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

Signed Stephen J. Pfeifer (TECHNICIAN)

DATE 3-23-89 INV. NO. 24207