

1090143

*R*

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 151-21,398 *00-45*  
C SE NW, SEC. 32, T 27 S, R 13 W ~~X~~

1980 feet from N/X section line

1980 feet from W ~~X~~ section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5087

Lease Name Humble Well # 1-32

Operator: Texas Energies, Inc.

County Pratt

Name & Address P. O. Box 947

Well Total Depth 4565. 148.37 feet

Pratt, KS 67124

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 432

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Wheatstate Oilfield Services License Number 5149

Address P. O. Box 329, Pratt, KS 67124

Company to plug at: Hour: 6:00 pm Day: 15 Month: March Year: 19 84

Plugging proposal received from Greg Bailey

(company name) Wheatstate (phone) 316-672-7514

were: \_\_\_\_\_ to fill hole with heavy mud and spot cement through drill pipe

1st plug at 720' with 70 sx cement  
solid bridge

2nd plug hulls - plug at 40' -- cement to surface with 10 sx cement

4th plug to circulate rathole with 15 sx cement

Plug water well with 5 sx cement.

Plugging Proposal Received by R Bearlutton  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 7:15 pm Day: 15 Month: March Year: 1984

ACTUAL PLUGGING REPORT 1st plug at 720' with 70 sx cement, 2nd & 3rd plugs - solid  
bridge - hulls - plug at 40' -- cement to surface with 10 sx cement, 4th plug to  
circulate rathole with 15 sx cement. Plug waterwell with 5 sx cement.

Remarks: Use 60/40 Pozmix 2% gel 3% cc by Halliburton  
(if additional description is necessary, use BACK of this form.)

**INVOICED**

DATE 3-22-84

INV. NO. 0895

*hwo*  
*03-22-84*

Signed R Bearlutton  
(TECHNICIAN)