

1 050399

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 151-21,511-00-00
100' NW of
SE SE NW, SEC: 29; T 27 S, R 13 W/E
3041 feet from S section line
3041 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5565

Lease Name Honeman Well # 1

Operator: National Cooperative Refinery Asso.
Name & Address: P. O. Box 6
Great Bend, KS 67530

County 0 Pratt 148.20

Well Total Depth 4560 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 375

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Kaw Drilling Company License Number 6739

Address 1010 Union Center, Wichita, KS 67202

Company to plug at: Hour: 4:00 pm Day: 10 Month: December Year: 19 84

Plugging proposal received from Lyle Juergensen

(company name) Kaw (phone) 316-264-0316

were: to fill hole with heavy mud and spot cement through drill pipe RECEIVED

1st plug at 4450' with 50 sx cement

2nd plug at 810' with 50 sx cement

3rd plug at 420' with 40 sx cement

4th plug solid bridge hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by Richard W. Lucas (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 6:30 pm Day: 10 Month: December Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 4450' with 50 sx cement, 2nd plug at 810' with 50

sx cement, 3rd plug at 420' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls -

plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with

15 sx cement.

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Halliburton

(If additional description is necessary, use BACK of this form.)

I (did/did not) observe this plugging.

DATE 12-18-84

INV. NO. 6014

Signed Richard W. Lucas (TECHNICIAN)

NOTICE OF INTENTION TO DRILL
(see rules on reverse side)

CORRECTED
CARD MUST BE SIGNED
11-27-84

Starting Date: November 19, 1984
month day year

OPERATOR: License # 5565
Name National Cooperative Refinery Assoc.
Address Box 6
City/State/Zip Great Bend, Kansas 67530
Contact Person I. J. Gotsche
Phone 316 793-7824

CONTRACTOR: License # 6739
Name Kaw Drilling Company
City/State Wichita, Kansas

Well Drilled For: Well Class: Type Equipment:
 Oil Sand Infield Mud Rotary
 Gas Inj Pool Ext. Air Rotary
 OWWO Expl Wildcat Cable

If OWWO: old well info as follows:
Operator
Well Name
Comp Date Old Total Depth
Projected Total Depth 4550 feet
Projected Formation at TD Arbuckle

Producing Formations L-KC-Simp-Miss-Arb.
Will comply with K.S.A. 55-101, et seq., plus eventually plug and hole to K.C.C. specifications.

to 11/20/84 Signature of Operator or Agent
I. J. Gotsche
I. J. Gotsche

API Number IS- 151-21,511-00-00
100' NW of East
SE. SE. NW... Sec. 29 Twp. 27 S. Rge. 13 West

* 3041 Ft North from Southeast Corner of Section
* 3041 Ft West from Southeast Corner of Section
(Note: Locate well on Section Plat on reverse side)

Nearest lease or unit boundary line 330 feet.
County Pratt
Lease Name Honeman Well# 1

Domestic well within 330 feet: yes no
Municipal well within one mile: yes no

Depth to Bottom of fresh water 150 feet
Lowest usable water formation Top of Permian
Depth to Bottom of usable water 250 feet

Surface pipe by Alternate: 1 2
Surface pipe to be set 350 feet
Conductor pipe if any required None feet
Ground surface elevation feet MSL.

This Authorization Expires 5-6-85
Approved by *[Signature]* 11-6-84
Kwas 2970 FSL
2970 FSL
District Supt.

RECEIVED
STATE CORPORATION COMMISSION
DEC 12 1984
CONSERVATION DIVISION
Wichita, Kansas