

To: 1 120067
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

2-15-88 101
API NUMBER 15-151-21,876-00-00
C SE SE, SEC. 29, T 27 S, R 13 W/R
660 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9408

Lease Name Honeman "A" Well # 1

Operator: Trans Pacific Oil Corporation
Name & Address: 410 One Main Place
Wichita, KS 67202

County Pratt 147.55
Well Total Depth 4540 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 330

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Trans Pac Drilling, Inc. License Number 5841

Address 410 One Main Place, Wichita, KS 67202

Company to plug at: Hour: 4:30 a.m. Day: 15 Month: 2 Year: 19 88

Plugging proposal received from Gary Pugh

(company name) Trans Pac Drilling, Inc. (phone) 316-265-0226

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 770-89'

1st plug at 790' with 50 sx cement, 2nd plug at 360' with 50 sx cement,

3rd plug at 40' with 10 sx cement.

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 15 sx cement.

Plugging Proposal Received by Duane Rankin
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 5:30 a.m. Day: 15 Month: 2 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug at 790' with 50 sx cement,

2nd plug at 360' with 50 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 15 sx cement,

Water well plugged with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(if additional description is necessary, use BACK of this form, Kansas)

Observe this plugging.

INVOICED

DATE 2-22-88

Signed Duane Rankin
(TECHNICIAN)

INV. NO. 19902

