

8-21

2-050730

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER: 15-035-23,201 0000

NE SW SE , SECTION 31 TOWNSHIP 32 RANGE 4E

OPERATOR LICENSE # 5998 990 FEET FROM S SECTION LINE
OPERATOR KEITH D. LEAKE 1815 FEET FROM E SECTION LINE
NAME & R.R. 3, BOX 160
ADDRESS WINFIELD, KS 67156

LEASE NAME: JOHNSON "A" #1
COUNTY: COWLEY 106.28
WELL TOTAL DEPTH: 3270' PB 3260'
PIPE: 4 1/2" @ 3269'
SURFACE CASING: 8 5/8" @ 216'

ABANDONED OIL WELL X GAS WELL INPUT WELL SWD D&A

OTHER WELL AS HEREINAFTER INDICATED:

PLUGGING CONTRACTOR: COOPER SERVICE COMPANY

ADDRESS: P.O. BOX 381, WINFIELD, KS 67156 LICENSE: 31865

COMPANY TO PLUG AT: HOUR: 8:00 DAY: 21 MONTH: 8 YR: 1997

PLUGGING PROPOSAL RECEIVED FROM: DISTRICT II

COMPANY NAME: DANIELS REDI-MIX PHONE: (316) 221-0906

WERE: SAND BACK AND SPOT 4 SACKS OF CEMENT AT 3160'. SHOOT 4 1/2" CASING AT 1800' AND PULL OUT OF HOLE. RUN TUBING TO 250' AND CIRCULATE CEMENT SLURRY TO SURFACE. PULL TUBING OUT OF HOLE AND TOP OFF WITH CEMENT.

PLUGGING PROPOSAL RECEIVED BY: ALBERT COOPER

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART (X) NONE ()

COMPLETED: HOUR: 10:00 DAY: 21 MONTH: 8 YEAR: 1997

ACTUAL PLUGGING REPORT: SANDED BACK AND SPOTTED 4 SACKS OF CEMENT AT 3160'. SHOT 4 1/2" CASING AT 1825' AND PULLED OUT OF HOLE. RAN TUBING TO 250' AND CIRCULATED CEMENT SLURRY TO SURFACE. PULLED TUBING OUT OF HOLE AND TOPPED OFF WITH CEMENT.

REMARKS: 109 SACKS CEMENT SLURRY DANIELS #51602

RECEIVED
KANSAS CORPORATION COMMISSION

OCT 03 1997

CONSERVATION DIVISION
WICHITA, KS

I DID OBSERVE THIS PLUGGING.

JERRY CLARK

INVOICED

DATE 10-3-97

INV. NO. 49207