

7-16

2-050986

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER: 15-035-23,286 0000
SE NE SW, SECTION 31 TOWNSHIP 32 RANGE 4E

OPERATOR LICENSE # 5710 FEET FROM S SECTION LINE
FEET FROM E SECTION LINE

OPERATOR McNeish Oil Company
NAME & ADDRESS P. O. Box 734
Winfield, KS 67156

LEASE NAME: Johnson #B-1
COUNTY: Cowley
WELL TOTAL DEPTH: 3275' 106.44

CONDUCTOR PIPE: @
SURFACE CASING: 8-5/8" @ 206'

ABANDONED OIL WELL GAS WELL INPUT WELL SHD D&A

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: B & S Well Service
ADDRESS: Box 837, Winfield, KS LICENSE: 6013

COMPANY TO PLUG AT: HOUR: _____ DAY: _____ MONTH: 7 YR: 1990

PLUGGING PROPOSAL RECEIVED FROM: _____
COMPANY NAME: _____ PHONE: _____

WERE: 5-1/2" casing set @ 3274' w/100 sx cmt & perf @ 3225'
to 3235' - sand back to 3200' & dump 5 sx cmt - shoot
& pull casing - circ cmt from 300' to surface.

PLUGGING PROPOSAL RECEIVED BY: Dist #2 Office

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL { } PART { } NONE { }

COMPLETED: HOUR: 3:00p DAY: 16 MONTH: 7 YEAR: 1990

ACTUAL PLUGGING REPORT:
Sanded back to 3175' & dumped 5 sx cmt w/dump bailer
- shot & pulled 2027' of 5-1/2" csg - built bridge @
375-350' & filled to surface w/cmt slurry.

REMARKS: _____

I DID NOT OBSERVE THIS PLUGGING.

INVOICED

DATE 7-26-90

INV. NO. 28757

Glenn Ward
Glenn Ward (AGENT)

STATE CORPORATION COMMISSION
CONSERVATION DIVISION
WICHITA, KANSAS

JUL 24 1990
07-24-90
WICHITA, KANSAS

FORM CP-2/3

MK