

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-151-00480-00-00 01 ab. 12/5/01
Spot: CSESW Sec/Twnshp/Rge: 26-27S-13W
4620 feet from N Section Line, 1980 feet from W Section Line
Lease/Unit Name: MONTFORD OWWO Well Number: 1
County: PRATT Total Vertical Depth: 4472 feet

Operator License No.: 5893
Op Name: PRATT WELL SERVICE, INC.
Address: PO BOX 847
PRATT, KS 67124

Conductor Pipe: Size _____ feet:
Surface Casing: Size 8.625 feet: 303 WITH 259 SX CMT
Production: Size 4.5 feet: 2840 WITH 125 SX CMT
Liner: Size _____ feet: _____

8/45.57

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/30/2001 3:30 PM

Plug Co. License No.: 5893 Plug Co. Name: PRATT WELL SERVICE, INC.

Proposal Rcvd. from: KEVIN GATES Company: PRATT WELL SERVICE, INC. Phone: (316) 672-2531

Proposed Plugging Method: SANDED BACK TO 2180' & 4 SX CMT. 1ST PLUG AT 750' WITH 50 SX CMT. 2ND PLUG AT 330' WITH 50 SX CMT. 3RD PLUG AT 0-40' WITH 10 SX CMT. USE 8 SX GEL FOR SPACER.

Plugging Proposal Received By: SCOTT ALBERG
Date/Time Plugging Completed: 08/30/2001 4:45 PM

WitnessType: Plugging Operations 100% Witnessed (Complete)
KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PBTD 2950'. PERFS AT 2638-42'. SANDED BACK TO 2180' & PUT 4 SX CMT ON TOP OF SAND BRIDGE THROUGH BAILER. SPOT PLUGS THROUGH 4 1/2" CASING. 1ST PLUG AT 750' WITH 8 SX GEL & 50 SX CMT. 2ND PLUG AT 330' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

RECEIVED
SEP 11 2001
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ACID SERVICES. RECOVERED 2118' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

Signed

Stephen J. Pfeifer
(TECHNICIAN)

INVOICE

DATE 9-11-01 SEP 05 2001

NO. 2002060458

Form ST-33