

1 030252

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 151-21,173 - 00-00

NW NW SE , SEC. 9 , T 27 S, R 14 ^{W/E}
2310 feet from ~~XXX~~ SE Corner of section line
2310 feet from ~~XXX~~ W SE Corner of section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5313

Lease Name Reschke "A" Well # 1

Operator: F & M Oil Co., Inc.
Name & Address 422 Union Center
Wichita, KS 67202

County Pratt

Well Total Depth 4670 151.78 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 328

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 12:30 pm Day: 20 Month: August Year: 19 84

Plugging proposal received from Clay Duntz

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" set at 4475' PBD 4447' Perfs 3928-36'

1st plug sand back to 3880' and dump 4 sx cement on top of sand through bailer

2nd plug pump 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls and 150 sx cement.

Plugging Proposal Received by Steve Almont
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 2:30 pm Day: 20 Month: August Year: 19 84

ACTUAL PLUGGING REPORT 4 1/2" set at 4475' PBD 4447' Perfs 3928-36'

1st plug sanded back to 3880' and dumped 4 sx cement on top of sand through bailer.

2nd plug pumped 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls and 150 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

Maximum pressure 300 psi and shut in pressure 50 psi.

08-24-84 AUG 24 1984

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Recovered 2405' 4 1/2" casing. Used 60/40 Pozmix 2% gel 3% cc by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

DATE 8-27-84

Signed Steve Almont
(TECHNICIAN)

SD

INV. NO. 3394