

To: 1 040637 3-26
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-151-22,081-00-00 176 R
SW SE SW, SEC. 32, T. 27 S, R 14 W/E
330 feet from S section line
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 6039
Operator: L.D. Drilling, Inc.
Name & Address: RR 1, Box 183 B
Great Bend, KS 67530

Lease Name Seyfert Well # 1
County Pratt
Well Total Depth 2694 89.55 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 331

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor L.D. Drilling, Inc. License Number 6039

Address RR 1, Box 183 B, Great Bend, KS 67530

Company to plug at: Hour: 1:45 p.m. Day: 25 Month: 3 Year: 19 92

Plugging proposal received from Greg Davidson

(company name) L.D. Drilling, Inc. (phone) 316-793-3051

work: to fill hole with heavy mud and spot cement through drill pipe. Anhydrite 916-36'
Lost circulation at 1035', squeezed 4 times at this depth.

1st plug at 1000' with 50 sx cement, tag cement,

2nd plug at 360', with 50 sx cement,

3rd plug at 40-0' with 10 sx cement, 4th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 12:45 a.m. Day: 26 Month: 3 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug spotted 50 sx cement at 900'-Thixotropic, tagged at 1025',

2nd plug spotted 50 sx cement at 900', 2 sx hulls and 1 sx hulls in cement, Thixotropic,

tagged at 965'. 3rd plug spotted 35 sx 60/40 Pozmix 3% gel 1/2# local 900', 150# hulls

with cement and 50# with cement. Hole stayed full.

4th plug spotted 50 sx cement at 360' with 60/40 Pozmix 6% gel

5th plug at 40-0' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement.

Remarks: Cemented by Halliburton.
(if additional description is necessary, use BACK of this form.)

Observe this plugging.

INVOICED DATE 4-22-92

INV. NO. 34980

Signed [Signature] (TECHNICIAN)

RECEIVED STATE CORPORATION COMMISSION MAR 27 1992 CONSERVATION DIVISION Wichita, Kansas

03.27.92

EFFECTIVE DATE: 3-22-92

DISTRICT # 1

SGA? Yes No

State of Kansas 15
NOTICE OF INTENTION TO DRILL 151-22,081-00-00

FORM MUST BE TYPED
FORM MUST BE SIGNED
ALL BLANKS MUST BE FILLED

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date .. March .. 17 .. 1992 ..
month day year

Spot SW SE SW Sec 32 Twp 27S S, Rg 14 X East West

OPERATOR: License # 6039
Name: L. D. DRILLING, INC.
Address: R.R. 1 Box 183 B.
City/State/Zip: Great Bend, KS 67530
Contact Person: L. D. Davis
Phone: (316) 793-3051

330 feet from South North line of Section
3630 feet from East West line of Section
IS SECTION REGULAR IRREGULAR?

(NOTE: Locate well on the Section Plat on Reverse Side)

County: PRATT
Lease Name: SEYFERT Well #: 1
Field Name: McBride

CONTRACTOR: License #: 6039
Name: L. D. Drilling, Inc.

Is this a Prorated/Spaced Field? yes no

Target Formation(s): Simpson
Nearest lease or unit boundary: 330'

Well Drilled For: Well Class: Type Equipment:
 Oil ... Enh Rec Infield Mud Rotary
 Gas ... Storage ... Pool Ext. ... Air Rotary
 OGW0 ... Disposal ... Wildcat ... Cable
 Seismic; ... # of Holes ... Other

Ground Surface Elevation: applied for feet MSL
Water well within one-quarter mile: yes no

Public water supply well within one mile: yes no
Depth to bottom of fresh water: 160'

Depth to bottom of usable water: 200'
Surface Pipe by Alternate: 1 2

Length of Surface Pipe Planned to be set: 300'
Length of Conductor pipe required: none

If OGW0: old well information as follows:

Projected Total Depth: 4650'
Formation at Total Depth: Simp

Operator: _____
Well Name: _____
Comp. Date: _____ Old Total Depth _____

Water Source for Drilling Operations:
 well farm pond other

Directional, Deviated or Horizontal wellbore? yes no
If yes, true vertical depth: _____

DWR Permit #: NA
Will Cores Be Taken?: yes no
If yes, proposed zone: _____

Bottom Hole Location: _____

Exp. 9/17/92

AFFIDAVIT

240' Alt. IReq.

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.

It is agreed that the following minimum requirements will be met:

Pusher Greg Davidson
SPUD DATE 3-20-92 INIT. SM
LENGTH SURFACE PLANNED 300'
RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.
RATHOLE AHEAD? Y N SIZE HOLE
SURFACE PIPE @ _____ CONDUCTOR
ANHYDRITE T- 716 B- 936 ELEVATION
Low Calc 1035 Spud 4 10000
TD 2694 FORMATION F.L. 1000'
RAN PIPE 8 3/8 @ 331 DV TOOL ALT II DONE
SX SX Y N
Arbuckle Plug @ _____ Ft. W/ SX
Hug./Council @ _____ Ft. W/ SX
1 Anhydrite Base @ 1000' Ft. W/ 50 SX
900' Ft. W/ 746' SX
2 1/2, 1/2 Plug @ 560 Ft. W/ 50 SX
Bottom Surface @ _____ Ft. W/ SX
3 40' Plug @ 40-0 Ft. W/ 10 SX 2
RAT HOLE CIRC/W/ S SX MOUSE HOLE W/ SX
WATER WELL _____ SX (Irr. Well) Pond _____
Hauling _____
TECHNICIAN _____ DATE _____
TYPE OF CEMENT 60/40 6% - 2-3% cc
STARTING TIME _____ : _____ (AM/PM) DATE _____
COMPLETION TIME _____ : _____ (AM/PM) DATE _____
CEMENT COMPANY Halliburton - 2 ml.