

1080274

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-Not available R

TECHNICIAN'S PLUGGING REPORT

990 feet from S section line
4950 feet from E section line

Operator License # 9514

Lease Name Becker Well # A-1

Operator: D & D Productions
Name & Address: P. O. Box 321
Pratt, KS 67124

County Pratt 154.38

Well Total Depth 4750 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 337

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 2:00 pm Day: 3 Month: December Year: 19 84

Plugging proposal received from Mike Gomez

(company name) Kelso (phone) 316-938-2457

were: 5 1/2" set at 4713' PBD 3235' Perfs at 3224-32'

1st plug sand back to 3175' and dump 5 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,

and 125 sx cement. Plug water well with 10 sx cement

RECEIVED
DEC 12 1984

Plugging Proposal Received by J. H. Metz
CONSERVATION DIVISION
Wichita, Kansas
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3:15 pm Day: 3 Month: December Year: 19 84

ACTUAL PLUGGING REPORT 5 1/2" set at 4713' PBD 3235' Perfs at 3224-32'

1st plug sanded back to 3175' and dumped 5 sx cement on top of sand through bailer,

2nd plug squeezed well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,

and 125 sx cement. Plugged water well with 10 sx cement

maximum pressure 400 psi and shut in 100 psi

Remarks: Recovered 3100' 5 1/2" casing. Used 60/40 Pozmix 2% gel 3% cc by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED
DATE 12-20-84
INV. NO. 6061

observe this plugging.

Signed J. H. Metz
(TECHNICIAN)