

1 090163

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-151-21,403-00-00

SW SW SW, SEC. 20, T. 27 S, R. 14 ~~W~~XX

330 feet from ~~XX~~S section line

330 feet from ~~W~~XX section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5087

Lease Name Jones Well # 1-20

Operator: Texas Energies, Inc.

County Pratt

Name & Address P. O. Box 947

Well Total Depth 4560 / 4820 feet

Pratt, KS 67124

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 389

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Wheatstate Oilfield Services License Number 5149

Address P. O. Box 329, Pratt, KS 67124

Company to plug at: Hour: 5:00 am Day: 16 Month: May Year: 19 84

Plugging proposal received from Dennis Petz

(company name) Wheatstate (phone) 316-672-7514

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 900' with 50 sx cement

2nd plug at 450' with 40 sx cement
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rathole with 15 sx cement

6th plug to circulate mousehole with 10 sx cement.

Plug water well with 5 sx Plugging Proposal Received by R. B. Barburton
cement (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 7:30 am Day: 16 Month: May Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 900' with 50 sx cement, 2nd plug at 450' with 40

sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface

with 10 sx cement, 5th plug to circulate rat hole with 15 sx cement, 6th plug to

circulate mouse hole with 10 sx cement, and plug water well with 5 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

Remarks: Use 60/40 Pozmix 2% gel 3% cc by Halliburton

MAY 17 1984

INVOICED

if additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION
Wichita, Kansas

DATE 5-21-84

INV. NO. 1583

5-16

Signed R. B. Barburton
(TECHNICIAN)