

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-033-21087-00-00
Spot: SESESESW Sec/Twnshp/Rge: 2-32S-18W
150 feet from S Section Line, 2500 feet from W Section Line
Lease Name: LYTLE A Well #: #1
County: COMANCHE Total Vertical Depth: 5797 feet

Operator License No.: 30481
Op Name: APOLLO ENERGIES, INC.
Address: 10378 N 281 HWY
PRATT, KS 67124

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	5336	3000	WITH 125 SX CMT
SURF	8.625	675		WITH 225 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 12/01/2014 8:30 AM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Rcvd. from: MARK MORGENSTERN Company: CLARKE CORPORATION Phone: (620) 886-5665

Proposed Plugging Method: SAND BACK TO 5100' WITH 5 SX CMT. PLUG AT 1020' WITH 10 SX GEL & 50 SX CMT. PLUG AT 700' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: _____ WitnessType: NONE
Date/Time Plugging Completed: 12/01/2014 11:00 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SANDED BACK TO 5100' & TOPPED WITH 5 SX CMT. TAGGED AT 5050'. 1ST PLUG AT 1008' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 693' WITH 50 SX CMT. 3RD PLUG AT 62' WITH 20 SX CMT. CMT CIRCULATED & HOLE STAYED FULL.

Perfs:

Top	Bot	Thru	Comments
5157	5180		

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID & CEMENT.

Plugged through: TBG

12/17/14 ckm

District: 01

Signed Eric MacLaren
(TECHNICIAN)

RECEIVED
DEC - 5 2014
KCC DODGE CITY

KCC WICHITA
DEC 12 2014
RECEIVED

Form CP-2/3