

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-195-22975-00-00  
Spot: NWNESESW Sec/Twnshp/Rge: 9-14S-22W  
1250 feet from S Section Line, 2220 feet from W Section Line  
Lease Name: MARLA KAY Well #: 1  
County: TREGO Total Vertical Depth: 4350 feet

Operator License No.: 34530  
Op Name: BOW CREEK OIL COMPANY, GENERA  
Address: 1304 EISENHOWER RD.  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	223		150 SX

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/28/2014 12:00 AM  
Plug Co. License No.: 31548 Plug Co. Name: DISCOVERY DRILLING  
Proposal Rcvd. from: TOM Company: DISCOVERY DRILLING Phone: (785) 623-2920

Proposed Plugging Method: Ordered 305 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: MARVIN MILLS WitnessType: NONE  
Date/Time Plugging Completed: 11/28/2014 5:30 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

1st plug @4278 w/50 sx  
2nd plug @1735 w/50 sx  
3rd plug @820 w/100 sx  
4th plug @275 w/50 sx  
5th plug @40 w/10 sx  
  
Rathole 30 sx Mousehole 15 sx

Perfs:

Remarks: QUALITY

Plugged through: DP

District: 04

Signed \_\_\_\_\_

(TECHNICIAN)

CM

KCC WICHITA

DEC 16 2014

RECEIVED

Form CP-2/3

DEC 11 2014

12/17/2014 CKM