

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-063-22019-00-00
Spot: SESENWSE Sec/Twnshp/Rge: 32-13S-29W
1470 feet from S Section Line, 1605 feet from E Section Line
Lease Name: OTTLEY Well #: 1
County: GOVE Total Vertical Depth: 4508 feet

Operator License No.: 9090
Op Name: CHARTER ENERGY, INC.
Address: PO BOX 252
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4528		150 SX
SURF	8.625	263		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/10/2014 10:00 AM
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING
Proposal Rcvd. from: CHRIS SCHOENHOFER Company: QUALITY OIL WELL CEMENTING Phone: (620) 793-9090

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement, 13 sx gel and 400 # hulls.
PC at 2285' w/450 sx cement.
Perforations at 4073' - 4147'.

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/10/2014 2:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Tied on to casing and pumped 75 sx cement w/400 # hulls, followed by 12 sx gel, followed by 220 sx cement. Topped off casing with 25 sx cement full. Backside cemented to surface.
GPS: 38.87723 -100.56291

Perfs:

Top	Bot	Thru	Comments
4141	4147		
4110	4118		
4073	4147		

Remarks: CHARTER ENERGY

Plugged through: CSG

District: 04

Signed [Signature]
(TECHNICIAN)

CM

DEC 11 2014

KCC WICHITA
DEC 16 2014
RECEIVED