

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-063-22021-00-00
Spot: NWNESESW Sec/Twnshp/Rge: 33-13S-29W
1165 feet from S Section Line, 2240 feet from W Section Line
Lease Name: OTTLEY Well #: 2
County: GOVE Total Vertical Depth: 4405 feet

Operator License No.: 9090
Op Name: CHARTER ENERGY, INC.
Address: PO BOX 252
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4426		150 SX
SURF	8.625	252		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/10/2014 8:00 AM
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING
Proposal Rcvd. from: CHRIS SCHOENHOFER Company: QUALITY OIL WELL CEMENTING Phone: (620) 793-9090

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement, 13 sx gel and 400 # hulls.
PC at 2226' w/160 sx cement.
Perforations: 3990' - 4048', 4291' - 4296' and 4383' - 4393'.

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/10/2014 10:45 AM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Tied on to casing and pumped 75 sx cement w/200 # hulls, followed by 12 sx gel, followed by 365 sx cement. Casing full. Tied on to backside and squeezed w/10 sx cement. Shut in pressure 200 psi.

GPS: 38.87635 -100.54942

Perfs:

Top	Bot	Thru	Comments
4383	4393		
4291	4296		
4042	4048		
4010	4014		
3990	4048		

Remarks: QUALITY CEMENT TICKET # 734

Plugged through: CSG

District: 04

Signed 12/17/14
(TECHNICIAN) CM

DEC 11 2014

KCC WICHITA
DEC 16 2014
RECEIVED