

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-055-00203-00-00
Spot: SW Sec/Twnshp/Rge: 24-21S-34W
1320 feet from S Section Line, 1320 feet from W Section Line
Lease Name: MOSS GAS UNIT Well #: 1
County: FINNEY Total Vertical Depth: 2612 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, LLC
Address: 6100 N WESTERN AVE PO BOX 18496
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2610	0	WITH 900 SX CMT
SURF	8.625	276		WITH 175 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/25/2014 9:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: DENNIS FRICK Company: CHESAPEAKE OPERATING Phone: (620) 277-0803

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK Witness Type: NONE
Date/Time Plugging Completed: 11/25/2014 11:00 AM KCC Agent: KEN JEHLIK

Actual Plugging Report:

Perfs:

FILL 5 1/2" CASING WITH CMT FROM 2572' TO 0' USING 230 SX CMT & 300# HULLS.
PRESSURE TO 600#. HOLDING. PUMP 15 SX CMT DOWN THE ANNULUS TO 200#.
TOP OFF 5 1/2" CASING WITH 5 SX CMT.

Remarks: USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: CSG

District: 01

Signed

[Signature]

(TECHNICIAN)

KCC WICHITA

DEC 12 2014

RECEIVED

RECEIVED

DEC - 4 2014

KCC DODGE CITY

12/17/14 *CKM*

[Signature]