

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-055-21710-00-00
Spot: N2NWSESW Sec/Twnshp/Rge: 20-23S-31W
1250 feet from S Section Line, 3630 feet from E Section Line
Lease Name: SEEDLE BRANCH Well #: 2-20
County: FINNEY Total Vertical Depth: 2800 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, LLC
Address: 6100 N WESTERN AVE PO BOX 18496
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2800	0	WITH 700 SX CMT
SURF	8.625	366		WITH 225 SX CMT

Well Type: HI UIC Docket No: _____ Date/Time to Plug: 11/25/2014 12:00 PM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: DENNIS FRICK Company: CHESAPEAKE OPERATING Phone: (620) 277-0803

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK WitnessType: NONE
Date/Time Plugging Completed: 11/25/2014 2:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

FILL 4 1/2" CASING WITH CMT FROM 2679' TO 0' USING 175 SX CMT & 250# HULLS.
PRESSURE TO 500#. HOLDING. PUMP 3 SX CMT DOWN THE ANNULUS TO 250#.

Perfs:

Top	Bot	Thru	Comments
2677	2679		
2662	2671		

Remarks: USED 60/40 POZMIX 4% GEL BY CONSOLDIATED.

Plugged through: CSG

District: 01

Signed

[Signature]
KCC WICHITA

(TECHNICIAN)

DEC 12 2014

RECEIVED

12/17/14 ccm

[Signature]

RECEIVED
DEC - 4 2014
KCC DODGE CITY