

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-055-00316-00-00
Spot: NE Sec/Twnshp/Rge: 13-22S-34W
3976 feet from S Section Line, 1295 feet from E Section Line
Lease Name: GARDEN CITY Well #: 1-13
County: FINNEY Total Vertical Depth: 2559 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, LLC
Address: 6100 N WESTERN AVE PO BOX 18496
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2535	0	WITH 100 SX CMT
SURF	8.625	296		WITH 200 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/24/2014 9:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: DENNIS FRICK Company: CHESAPEAKE OPERATING Phone: (620) 277-0803

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/24/2014 12:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 140 SX CMT WITH 300# HULLS TO 2542'. DISPLACE CMT TO 1025'.
PRESSURE TEST CASING TO 600#. HOLDING. PERFORATE 4 HOLES AT 1000'.
INJECTION RATE 3 BPM AT 1000#. PUMP 40 SX CMT, 50# HULLS THEN 40 SX CMT.
DISPLACE TO 600' AT 1000 PSI LEAVING 40 SX CMT OUTSIDE THE PERFS & 40 SX
CMT INSIDE THE CASING. PERFORATE 4 HOLES AT 350'. CIRCULATE CMT TO
SURFACE WITH 110 SX CMT LEAVING THE CASING & ANNULUS FULL OF CMT.

Perfs:

Top	Bot	Thru	Comments
2535	2542	OH	


Remarks: USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: CSG

12/17/14 ckm

District: 01

Signed



(TECHNICIAN)

RECEIVED

DEC - 3 2014

KCC DODGE CITY

KCC WICHITA

DEC 12 2014

RECEIVED

