


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD

Pratt County. Sec. 6 Twp. 27 Rge. 15 (E) (W)

Location as "NE/CNW/SW" or footage from lines NE NE NE
Lease Owner Musgrove Petroleum Corporation
Lease Name Tatlock Fee Well No. 1
Office Address 518 Petroleum Building, Wichita, Kansas.
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed May 13, 19 54
Application for plugging filed May 13, verbally 19 54
Application for plugging approved May 13, verbally 19 54
Plugging commenced May 13, 19 54
Plugging completed May 13, 19 54
Reason for abandonment of well or producing formation Dry hole



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes - verbally

Name of Conservation Agent who supervised plugging of this well _____
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4843 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	850'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Loaded hole with mud to 300'.
Set first plug at 300' with 1 1/2 gals cottonseed hulls & 20 sacks cement. Loaded hole with muc to 35'.
Set second plug with 1 1/2 gals cotton seed hulls & 10 sx cement.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Musgrove Petroleum Corporation
Address 518 Petroleum Building, Wichita, Kansas.

STATE OF Kansas, COUNTY OF Sedgwick
I, GORDON L. KOELLING (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Gordon L. Koelling
518 Petroleum Building, Wichita, Kansas.
(Address)

SUBSCRIBED AND SWORN TO before me this 18th day of May, 19 54

Alma E. Rans
Notary Public.

My commission expires July 16, 1955.

RECEIVED
STATE CORPORATION COMMISSION

MAY 18 1954
05-19-54
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 6 T 27 R 15 W
BOOK 34 PAGE 33

CONTRACTOR'S WELL LOG

COMPANY:	Musgrove Petroleum Corporation
CONTRACTOR:	Musgrove Petroleum Corporation
FARM:	Tatlock Fee #1
LOCATION:	NE NE NE, Section 6-27S-15W Pratt County, Kansas.
COMMENCED:	April 26, 1954
COMPLETED:	May 13, 1954

0	205	Sand, gravel & sandstone
205	240	Sandstone & sand streaks
240	265	Gray sticky shale
265	630	Shale, shells, red bed
630	1045	Shale & shells
1045	1060	Anhydrite
1060	1250	Red bed, shale & shells
1250	1880	Shale & red bed
1880	2110	Shale, shells & lime
2110	2290	Lime & shale
2290	2453	Lime
2453	3587	Lime & shale
3587	3650	Lime
3650	3792	Lime & shale
3792	3879	Lime
3879	4080	Lime & shale
4080	4119	Lime
4119	4230	Lime & shale
4230	4429	Lime
4429	4470	Mississippi
4470	4534	Lime
4534	4570	Lime & chert
4570	4843	Lime
	4843	Rotary Total depth

Set 8-5/8" surface pipe at 850' with 475 sacks of common cement and 6 calcium chloride

Dry and abandoned.

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

I, GORDON L. KOELLING, do hereby certify that the above and foregoing is a true and correct copy of the log of the Tatlock Fee #1, NE NE NE, Section 6-27S-15W, Pratt County, Kansas, as reflected by the files of the Musgrove Petroleum Corporation.

MUSGROVE PETROLEUM CORPORATION

BY Gordon L. Koelling
Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 18th day of May, 1954.

PLUGGING
TAX SEC 6 T 27 S 15 W
BOOK PAGE 34 LINE 33

Alma E. Rose
Notary Public

My commission expires July 16, 1955.

RECEIVED
STATE COMMISSION

CONSERVATION DIVISION