

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Pratt County, Sec. 36 Twp. 27 Rge. (E) 14 (W)

Location as "NE/CNW/SW" or footage from lines NE/4

Lease Owner Sterling Drilling Company & Carl F. Hertlein

Lease Name Elliott C-1 Well No. C-1

Office Address Sterling, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed June 27 19 57

Application for plugging filed June 27 19 57

Application for plugging approved June 27 19 57


Plugging commenced June 27 19 57

Plugging completed June 27 19 57

Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well R. M. Brundege

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	370'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud. Plugged bottom hole at 340' with 20 sacks cement. Top plug set at 40' with 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

JUL 3 1957

07-02-57

CONSERVATION DIVISION
STATE OF KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Group Exploration Company

Address Sterling, Kansas

STATE OF KANSAS COUNTY OF RICE ss.

F. A. Wuellner (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]

Sterling, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 1st day of July, 19 57

My Commission Expires Jan. 22, 1958

Bernard Laufermillh
Notary Public.

My commission expires _____

PLUGGING
FILE SEC. 36 T. 27 R. 14 W
BOOK PAGE 24 LINE 13

GROUP EXPLORATION COMPANY
Sterling, Kansas

WELL LOG ----- ELLIOTT C-1
Located: NE/4, Section 36-27-14W, Pratt County, Kansas

OWNER: Sterling Drilling Company, et al
ROTARY DRILLING CONTRACTOR: Group Exploration Company

COMMENCED: 6-7-57
COMPLETED: 6-27-57

TOTAL DEPTH: 4607'

LOG

0 - 120	Sand
120 - 795	Red Bed & Shale
795 - 815	Anhydrite
815 - 1200	Red Bed
1200 - 1650	Red Bed & Shale
1650 - 1890	Shale & Broken Lime
1890 - 2205	Lime
2205 - 2305	Lime & Shale
2305 - 2520	Lime
2520 - 3280	Lime & Shale
3280 - 3355	Lime
3355 - 3415	Lime & Shale
3415 - 3655	Lime
3655 - 3859	Shale
3859 - 4005	Lime L
4005 - 4030	K. C. Lime
4030 - 4065	Lime
4065 - 4110	Cherty Lime
4110 - 4140	K. C. Lime
4140 - 4185	Lime
4185 - 4215	Lime & Chert
4215 - 4330	Lime
4330 - 4360	Conglomerate
4360 - 4385	Miss. Chert
4385 - 4425	Lime & Shale
4425 - 4468	Lime
4468 - 4522	Reaming
4522 - 4525	Shale & Iron
4525 - 4565	Shale
4565 - 4580	Chert & Shale
4580 - 4607	Lime T. D.

CASING RECORD

Set 8-5/8" surface casing @ 370'
with 275 sacks cement, 3% c.c.

Plugged & Abandoned

RECEIVED
STATE CORPORATION COMMISSION

JUL 2 - 1957
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC. 36 T. 27 R. 14W
BOOK PAGE 24 LINE 13