

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
260 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER Unknown

LEASE NAME Krueger

WELL NUMBER 4

4130 Ft. from S Section Line

2747 Ft. from E Section Line  
SW NW NE1/4

SEC. 35 TWP. 27S RGE. 14W (E) or (W)

COUNTY Pratt

Date Well Completed \_\_\_\_\_

Plugging Commenced 12-15-88

Plugging Completed 3-27-89

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Pratt Well Service, Inc

ADDRESS P.O. Box 847 Pratt, Kansas 67124

PHONE# (316) 672-2531 OPERATORS LICENSE NO. 5893

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on March 9, 1989 (date)

by Dick Kapp-----Steve Pfeifer was on location. (KCC District Agent's Name).

Is ACO-1 filled? \_\_\_\_\_ If not, Is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom T.D. 4630-Shoe

PBTD 4328', 4701' open hole---Perfs: 4421-27

Show depth and thickness of all water, oil and gas formations. 4378-86

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | From | To   | Size   | Put In | Pulled out    |
|-----------|------|------|--------|--------|---------------|
|           | 0    | 430  | 10 3/4 |        | 0             |
|           | 430  | 4550 | 7"     |        | 2013' 53 jts. |
|           |      |      |        |        |               |
|           |      |      |        |        |               |

Describe in detail the formation in which the well was plugged, indicating where the mud fluid was placed and the methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set  
Dec. 15-22, 1988: Rigged up and pulled rods, pump, 139 jts. of 2 3/8" tubing, cut and pulled 2 1/16" tubing, recovered 136 jts. Sand was 4280 feet from surface, dumped 7 sx. cement, cut casing at 2013, third shot. Pulled and layed down 53 jts.  
3-15-89: 400# hulls, 12 gel, 60 sx, 12 gel, 100# hulls, 140 sx. cement, 60-40 p0z, 6%.  
Nax, 399# SUT 50#.  
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Pratt WELL Service, Inc. License No. 5893

Address Box 847 Pratt, Kansas 67124

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Pratt Well Service, Inc.


STATE OF Kansas COUNTY OF Pratt, ss.

Judy Berry plugging contractor  
(Employee of ~~XXXXXXXXXXXXXXXXXXXX~~) c  
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Judy Berry

(Address) Box 847 Pratt, Ks. 67124

SUBSCRIBED AND SWORN TO before me this 5th day of April, 19 89



My Commission Expires: February 6, 1993  
Dorothy M. Ferguson  
Notary Public