

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

File All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217

WELL PLUGGING RECORD

Locate well correctly on above
Section Plat

Pratt County, Sec. 28, Twp. 27S Rge. K01 13 (W)
 Location as "NE/CNW/SESW" or footage from lines NW SE NW
 Lease Owner Hummon Oil Company
 Lease Name Schaffer Well No. 1
 Office Address 1725 KSB&T Building, Wichita, Kansas 67202
 Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
 Date well completed December 29 19 76
 Application for plugging filed December 29 19 76
 Application for plugging approved December 29 19 76
 Plugging commenced December 29 19 76
 Plugging completed December 29 19 76
 Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well G. R. Biberstein
 Producing formation Depth to top Bottom Total Depth of Well 2203 Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded up with heavy mud to 300 feet. Followed by wooden plug and $\frac{1}{2}$ sack of hulls. Placed 35 sacks cement onto hulls. Mudded up with heavy mud to 40 feet followed by wooden plug, $\frac{1}{2}$ sack of hulls and 15 sacks cement to base of well cellar. Plugged rat hole with 5 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

JAN 06 1977

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
 Name of Plugging Contractor Graves Drilling Co., Inc.
 Address 910 Union Center, Wichita, Kansas 67202

STATE OF KANSAS COUNTY OF SEDGWICK 58.
 Betty Brandt (employee of owner) or (owner) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Betty Brandt

910 Union Center, Wichita, Ks.
(Address)

Subscribed and Sworn to before me this 5th day of January 1977

My commission expires June 17, 1977

Ruth N. Benjamin

Notary Public.

ROTARY DRILLERS LOG

OPERATOR: Hummon Oil Company
1725 KSB&T Building
Wichita, Kansas 67202

DRILLING COMMENCED: December 22, 1976

CONTRACTOR: Graves Drilling Co., Inc.
910 Union Center
Wichita, Kansas 67202

DRILLING COMPLETED: December 29, 1976

CASING RECORD: 10 Jts. 412' of used 8 5/8"
cemented with 275 sacks

LOCATION: Schaffer No. 1
NW SE NW
Section 28-27S-13W
Pratt County, Kansas

0 - 412 Sand and Red Bed
412 - 1100 Sand and Shale
1100 - 2095 Shale
2095 - 2203 Shale and Shells
2203 Rotary Total Depth

RECEIVED
STATE CORPORATION COMMISSION

JAN 06 1977

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify the foregoing statements to be true and correct to
the best of my knowledge.

GRAVES DRILLING CO., INC.

By Ruth N. Benjamin
Secretary-Treasurer

STATE OF KANSAS)
SEDGWICK COUNTY) ss.

Subscribed and sworn to before me, a Notary Public, this 5th day of
January, 1977.

Ruth N. Benjamin
Ruth N. Benjamin Notary Public

My commission expires: June 17, 1977