

15-175-20099-0000


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

Seward County, Sec. 7 Twp. 33S Rge. (E) 33 (W)
Location as "NE/CNW%SW%" or footage from lines C SW SW
Lease Owner Ferguson Oil Company
Lease Name Fitzgerald Well No. 1
Office Address 1120 Wichita Plaza, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed February 28, 19 70
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced February 28, 19 70
Plugging completed February 28, 19 70
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes (Edgar J. Eves, State Pluggger)

Name of Conservation Agent who supervised plugging of this well _____
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4420 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface Casing	0	1594'	8-5/8"	1594'	-----

RECEIVED
STATE CORPORATION COMMISSION
MAR 3 1970
CONSERVATION DIVISION
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Heavy Mud from Total Depth to 1000 Feet;
35 sax Cement from 1000 Feet to 900 Feet;
Mud to 45 Feet; Hulls & Plug @ 45 Feet and
15 sax Cement to Base of Cellar; 2 sax
Cement in Rat Hole. Job completed by
Halliburton @ 12:05 P.M. on 2/28/70.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Halliburton
Address Box 129, Liberal, Kansas 67901

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Wayne W. Kahmeyer of Sage Drilling Co. (employee of owner) or (owner or operator) of the above described well being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wayne W. Kahmeyer
500 Bitting Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of March, 19 70

My commission expires November 26, 1970

Louise K. Whitted
Louise K. Whitted - Notary Public.

DRILLERS LOGFITZGERALD NO. 1

CASING RECORD:	OPERATOR:	Ferguson Oil Co.	DESCRIPTION:
8-5/8" @ 1594'	CONTRACTOR:	Sage Drilling Co.	C SW SW
w/750 sax cement	COMMENCED:	February 18, 1970	Sec. 7-33S-33W
TOTAL DEPTH:	COMPLETED:	February 28, 1970	Seward County, Kansas
4420'			ELEVATION: 2874KB

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Soil	0	404	
Red Bed & Gyp	404	1070	
Sand, Red Bed, Shale & Anhydrite	1070	1595	
Anhydrite, Shale & Shells	1595	2191	
Lime & Shale	2191	4265	
Lime	4265	4353	
Lime & Shale	4353	4420	D&A

RECEIVED
STATE CORPORATION COMMISSION
MAR 3 1970
CONSERVATION DIVISION
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SAGE DRILLING CO., INC.

By Wayne W. Kahmeyer
Wayne W. Kahmeyer

Subscribed and sworn to before me this 2nd day of March, 1970.

Louise K. Whitted
Louise K. Whitted, Notary Public

My commission expires:
November 26, 1970.