

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Seward SEC. 7 TWP. 33S RGE. 33W ~~X~~/W
Location as in quarters or footage from lines:
1980' FSL & 1980' FWL - NE/SW

| | | | |
|--|--|--|--|
| | | | |
| | | | |
| | | | |
| | | | |

Lease Owner Midwestern Exploration
Lease Name Fitzgerald Well No. 1-7
Office Address P.O. Box 1869, Liberal, KS 67901
Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole (C)(L)
Date Well Completed 6/19/83
Application for plugging filed 6/20/83
Plugging commenced 6/18/83
Plugging completed 6/19/83
Reason for abandonment of well or producing formation Dry

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Clarence Thomas, Jr.
Producing formation St Louis Depth to top _____ bottom _____ T.D. 6400'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

| Formation | Content | From | To | Size | Put in | Pulled Out |
|---------------------|---------|---------|-------|--------|----------|------------|
| Red bed | | Surface | 650' | 8-5/8" | 1619.56' | None |
| Anhydrite & red bed | | 650' | 1620' | | | |
| Red bed & shale | | 1620' | 1830' | | | |
| Lime & shale | | 1830' | 6157' | | | |
| Basal Chester | | 6157' | 6215' | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Halliburton plugged with 60/40 POZ, 2% gel, 3% cc - 1st plug at 1680', 50 sx - 2nd plug at 640', 35 sx - 3rd plug at 40'-0' with wooden plug, 10 sx - 15 sx in rathole and 10 sx in mousehole


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton Services

STATE OF Kansas COUNTY OF Seward, ss.
R.F. Burke (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R.F. Burke
P.O. Box 1869, Liberal, KS
(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of June, 19 83



Linda Herron
Notary Public.

My Commission expires _____

RECEIVED
STATE CORPORATION COMMISSION

JUN 21 1983

CONSERVATION DIVISION
Wichita, Kansas