

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

API NUMBER 15-175-20782-0000

LEASE NAME Strickland

WELL NUMBER 1-7

3300 Ft. from S Section Line

1980 Ft. from E Section Line

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR Jack Reese, d/b/a Midwestern Exploration Co. SEC. 7 TWP. 33 SRGE. 33 (EXX) (W)

ADDRESS P.O. Box 1884, 111 E. 11th. St., Liberal, KS 67901 COUNTY Seward

PHONE# (316) 624-3534 OPERATORS LICENSE NO. 5263 Date Well Completed 12-6-84

Character of Well D&A Plugging Commenced 2-12-85

(Oil, Gas, D&A, SWD, Input, Water Supply Well) Plugging Completed 3-13-85

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? yes If not, is well log attached? \_\_\_\_\_

Producing Formation Basal Chester Depth to Top 6082 Bottom 6092 T.D. 6382

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Chester		Surface	1632	8-5/8	1632	
Toronto		Surface	6379	4 1/2	6379	2593

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set.  
Pumped 34 sx cement at 1630'. Capped well.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent's Casing Pulling Service License No. 6547

Address 620 S. Lincoln, Box 506, Liberal, Kansas 67901 STATE CORPORATION COMMISSION

STATE OF Kansas COUNTY OF Seward, ss.


Harold K. Frauli (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well was filed that the same are true and correct, so help me God.

(Signature) Harold K. Frauli

(Address) P.O. Box 1884, Liberal, KS 67901

NOTARY PUBLIC SUBSCRIBED AND SWORN TO before me this 12th day of April, 19 85

My Appointment Expires: 10-4-86  
Elaine Long  
 Notary Public



Commission Expires: \_\_\_\_\_

GABBERT-JONES, INC.  
-DRILLERS WELL LOG-

TRICKLAND PROSPECT  
Sec. 7-33S-33W  
Edward County, Kansas

Commenced: 10-08-84

Completed: 10-22-84


Operator: Midwestern Exploration Co.

From	Depth To	Formation	Remarks
0	70	Cased hole	70' of 20" csg.
70	460	Sand-Redbed	
460	1100	Sand	
100	1635	Sand-Redbed-Anhy	Ran 40 jts. of 24# 8 5/8" csg. set @ 1632' cemented w/ 200 sks. Posmix 2% Gel 1/4# Flocele - 2% CC
635	1840	Anhy-Redbed-Shale	150 sks. Common 2% CC
840	6380	Lime-Shale	PD @ 6:15 PM 10-9-84
6380	- TD		Ran 150 jts. of 10 1/2# 4 1/2" csg set @ 6379' DU Tool @ 4420 Cement Bottom w/ 50 sks Class H - 6% Gel 10% Salt 1/4# FC PD @ 5:00 AM 10-22-84 Cement Top w/50 sks. Common 6% Gel - 10% Salt - 1/4# Flocele 125 sks. of 50/50 Posmix w/ 18% Salt - 3/4 of 1% CFR2 PD @ 11:00 AM 10-22-84

State of Kansas )  
County of Sedgwick)

I, the undersigned, being duly sworn on oath, state that the above Drillers Well Log is true and correct to the best of my knowledge and belief and according to the records of this office.

GABBERT-JONES, INC.

  
James S. Sutton, II - President

Subscribed & Sworn to before me  
this 31st day of October, 1984.

  
Ola Lenore Costa

Commission expires November 21, 1984.

RECEIVED  
STATE CORPORATION COMMISSION

FEB 26 1985

CONSERVATION DIVISION  
Wichita, Kansas